



November 2024

Quotation

Supply, Deliver & Install

Adelaide Oval Turf Solutions

Goodwood oval - Cricket facility



P: +61 7 3394 4200 W: www.gabba.com.au E: info@gabba.com.au

Cost Breakdown

Goodwood oval - Cricket facility

Site establishment

Site Safety Documents Site

Site Safety temporary fencing

Copies of required Licences and Insurances

Temp fencing around the work site by A.O.T.S

Permanently display all relevant WHS and works signage on the temp fencing for the duration of the works.

All work to comply with AS 1725.4 Cricket Net Fencing Enclosures,

Set-out of cricket practice nets

Excavate footings as per AS 1725.4 & AS2870-2011

Install steel reinforcing as AS 1725.4 & AS2870-2011

Install uprights as per AS 1725.4 & AS2870-2011

Civil works 100-150mm deep x 55m wide x 36m long.

excavated soils to stay onsite & removed by A.O.T.S contractor.

\$6,860 + gst

Slabs & Footings:

Footings and reinforcing will be inspected by certifying rep. prior to concrete placement

1 x Install concrete slab 18m x 33m, Excavate 1% fall for drainage, F82 Reo mesh, 25 MPa concrete, 100mm thick, steel trowel finish.

1 x Rear path 55m x 3m F82 Reo mesh, 25 MPa concrete, 100mm thick, steel trowel finish.

1 x maintenance strip down the right side of the turf block between posts 33m x 1m F82 Reo mesh, 25 MPa concrete, 100mm thick, steel trowel finish.

\$18800

Gabba Grass & Nets

1 x Gabba Grass 10mm TEST 300 18m x 33m Installed -inc Complimentary Beige pitches 25m x 2.4m

24 x Adhesive 20lt

Fencing - Hard Wicket

Install perimeter chain wire security fencing - Black PVC

2 X 27m long x 18m wide x 3.6m high

4 x Internal Double mesh divider 21m between the lanes,



Full Length roof 27m Top wire roof, bottom rails - Gal

80nb end posts, 50nb mid posts, 32nb rails - Gal

Black pvc rip stop protection across the back & 9m up each side of the batting end of the public lanes

Turf block netting system

Install footings & steel posts / rails for the sideways retractable net system

8 x Engineered Pier footing

8 x Engineered SHS posts

6 x Engineered RHS rails

13 x 31m stainless cables

1 x retractable turf netting system - to suit 3 rotations of 4 pitches.

24.8m wide x 25m long x 4.0m high

stainless steel fitting & accessories

Clean Up Site

Remove any debris, concrete spoil & rubbish from site

Remove safety fencing

Trade - \$375,640 + GST

RRP - \$ 431,986 + GST

Total Price Excluding GST

\$375,640.00

Terms & Conditions

Payment terms: 50% deposit on purchase order, 25% on supply of materials on site and final 25% payment on completion and sign off.

Excludes: Council requirements (DA & BA) – Ex Gabba works.

CONDITIONS OF QUOTATION:

1. Please note that specifics of the quotation including prices and quantities are subject to confirmation prior to commencement of any work. Prices quoted cover only services nominated.
2. This quotation remains valid for 30 days from the quotation date.
3. If our quotation is accepted, work will be undertaken by employees of Gabba Sporting Products and /or our nominated sub-contractors.
4. The conditions of offer are shown in our quotation and our offer does not imply our willingness to enter into a sub-contract agreement containing conditions that differ from our offer.
5. All variations to contract must be made in writing, signed and approved by an authorised representative prior to additional work commencing.
6. Gabba Sporting Products has built its name on quality products & workmanship, all care will be taken whilst working on site. We do not accept any responsibility for any damage to buildings, services or surrounding landscapes as we will be working in conjunction with the property engineers & stakeholders.
7. It is the client's responsibility to mark out boundaries and/or have the boundary surveyed, and services such as Phone, Power, Water & Gas must be located by the client.
8. To facilitate vehicle and machine entry to the site, a suitable path is to be nominated by the client. The client is to provide ground protection mats in place if the path is soft & likely to be damaged.
9. Unless otherwise specified, quotations are based on standard soil conditions for excavation. In the event of rock, hard fill or foreign material being encountered, further costs as required for excavation / earthwork will be applied.
10. This quote is subject to site inspection. If the work site is found to contain unforeseen obstacles, resulting in need for additional earthwork, structural support etc., this quote will no longer be valid and a new quote will be issued.
11. All soil lifted during excavation will be moved within the grounds, no soil will be removed from the property, a suitable location will be arranged with the grounds staff prior to excavation work starting.
12. Whilst every effort is made to complete the works within a timely manner, deviation from the anticipated time frame may be encountered in unfavourable weather conditions or where unforeseen obstacles are encountered within the site.
13. Site specific inductions that exceed thirty (30) minutes in length will incur a charge based on our hourly rate.
14. In the event of a dispute, the client agrees to provide details of the dispute in writing within 7 days of receipt of our invoice. If no details are provided within this time, all due monies are to be paid as per our agreed trading terms.
15. Notwithstanding the Terms & Conditions outlined above, these terms will not negate any state or federal regulation in any way.
16. It is the customer's responsibility to ensure sufficient access, equipment, and personnel are available to unload the entire order from the truck.

Accepting the above works, items, notes & payment terms

Full Name: _____ Signature: _____ Date: _____

Kind Regards Mitch Gaskell

