



Quotation
Supply, Deliver & Install
Brisbane Grammar School

P: +61 7 3394 4200 W: www.gabba.com.au E: info@gabba.com.au

Cost Breakdown

8 Lane cricket facility - Northgate sports fields

Site establishment

Site specific engineering design

Site Safety Documents Site

Site Safety temporary fencing

Copies of required Licences and Insurances

Site Set-up

Provide for a Dial B4 U Dig search for the works area and locate all services onsite before commencement of site works by means of professional ground search.

Supply, install & maintain up to 120m of Safety Bunting fencing around the works site for the duration of the works. (As per construction site diagram).

Permanently display all relevant WHS and works signage on the fencing for the duration of the works.

Provide engineering design

Construction (As per engineers specifications)

Allowance for Engineer Review of Geotechnical Report

Set-out of cricket practice nets

Excavate footings as per engineers specifications & drawings

Install steel reinforcing as per engineers specs & drawings

Install uprights as per engineers specs & drawings

Existing 4 lane facility

Remove the posts, nets & synthetic grass

Clean back the slab & attend to any cracks with epoxy.

Slabs & Footings

Excavate area & place soils aside onsite in directed location.

Footings and reinforcing will be inspected by engineering rep. prior to concrete placement

Install 2 concrete slabs:

Install 140/m of 300 x 300 edge thickening beams

1) 36m Long x 14.5m wide new - 4 lane

2) 12m Long 14.5m wide - old 4 lane run up extension

Concrete specs - SL 82, 25mpa.



Synthetic Grass Covering

Install Gabba Grass covering to concrete area 1036.8 m²

Complimentary Beige pitches.

Install Gabba pitch map indicators to 4 pitches

Posts

Install 28 Engineered posts - Satin black

Netting - Fully enclosed facility

Install 9 Lane nets 25m long x 4.0m high - Internal nets retractable for multi sports use.

Install 1 back net 28.8m wide x 4.0 high

Install 1 front net 28.8m wide x 4.0 high

Install 2 side net 11m wide x 4.0 high

Install 1 full cover safety roof net 36m long x 28.8m wide with side safety curtain nets

Clean Up Site

Remove any rubbish from site

Remove temporary fence

Total Price Excluding GST

\$299,990.00



*Example of similar facility, not representative of quote

Terms & Conditions

Payment terms: 50% deposit on purchase order, 25% on install of concrete slab & final 25% payment on completion & sign off.

Excludes: Council requirements (DA & BA) – Ex Gabba works.

CONDITIONS OF QUOTATION:

1. Please note that specifics of the quotation including prices and quantities are subject to confirmation prior to commencement of any work. Prices quoted cover only services nominated.
2. This quotation remains valid for 30 days from the quotation date.
3. If our quotation is accepted, work will be undertaken by employees of Gabba Sporting Products and /or our nominated sub-contractors.
4. The conditions of offer are shown in our quotation and our offer does not imply our willingness to enter into a sub-contract agreement containing conditions that differ from our offer.
5. All variations to contract must be made in writing, signed and approved by an authorised representative prior to additional work commencing.
6. Gabba Sporting Products has built its name on quality products & workmanship, all care will be taken whilst working on site. We do not accept any responsibility for any damage to buildings, services or surrounding landscapes as we will be working in conjunction with the property engineers & stakeholders.
7. It is the client's responsibility to mark out boundaries and/or have the boundary surveyed, and services such as Phone, Power, Water & Gas must be located by the client.
8. To facilitate vehicle and machine entry to the site, a suitable path is to be nominated by the client. The client is to provide ground protection mats in place if the path is soft & likely to be damaged.
9. Unless otherwise specified, quotations are based on standard soil conditions for excavation. In the event of rock, hard fill or foreign material being encountered, further costs as required for excavation / earthwork will be applied.
10. This quote is subject to site inspection. If the work site is found to contain unforeseen obstacles, resulting in need for additional earthwork, structural support etc., this quote will no longer be valid and a new quote will be issued.
11. All soil lifted during excavation will be moved within the grounds, no soil will be removed from the property, a suitable location will be arranged with the grounds staff prior to excavation work starting.
12. Whilst every effort is made to complete the works within a timely manner, deviation from the anticipated time frame may be encountered in unfavourable weather conditions or where unforeseen obstacles are encountered within the site.
13. Site specific inductions that exceed thirty (30) minutes in length will incur a charge based on our hourly rate.
14. In the event of a dispute, the client agrees to provide details of the dispute in writing within 7 days of receipt of our invoice. If no details are provided within this time, all due monies are to be paid as per our agreed trading terms.
15. Notwithstanding the Terms & Conditions outlined above, these terms will not negate any state or federal regulation in any way.
16. It is the customer's responsibility to ensure sufficient access, equipment, and personnel are available to unload the entire order from the truck.

Accepting the above works, items, notes & payment terms

Full Name: _____ Signature: _____ Date: _____

Kind Regards Mitch Gaskell

