

May 2022

Quotation

Supply, Deliver & Install

Dalmeny Oval - Cricket NSW

2 Lane Cricket Facility



P: +61 7 3394 4200 W: www.gabba.com.au E: info@gabba.com.au

Cost Breakdown

2 Lane Cricket Facility

Site establishment

Site specific engineering design & certification

Site Safety Documents Site

Site Safety temporary fencing

Copies of required Licences and Insurances

Site Set-up

Provide for a Dial B4 U Dig search for the works area and locate all services onsite before commencement of site works by means of professional ground search.

Supply, install & maintain up to 90m of lockable temporary construction fencing around the works site for the duration of the works. (As per construction site diagram).

Permanently display all relevant WHS and works signage on the fencing for the duration of the works.

Provide engineering design and certification

Construction (As per engineers specifications)

Allowance for Geotechnical Report

Allowance for Engineer Review of Geotechnical Report

Remove the existing structure & synthetic grass

Set-out of cricket practice nets

Excavate footings as per engineers specifications & drawings

Install steel reinforcing as per engineers specs & drawings

Install uprights as per engineers specs & drawings

Slabs & Footings

Footings and reinforcing will be inspected by CN rep. prior to concrete placement

Install Gal fencing 3.6m high x 7.2m wide x 25m long. 3.15mm heavy duty wire. Double mesh to middle divider. 80nb end posts, 50nb mid posts, 32nb top & bottom rails. 3 mid belly cables.

1 x Canopy soft netting 7.2m x 25mt

Black pvc rip stop protection across the back & 6m up each side of the batting end

All work to comply with AS 1725.4 Cricket Net Fencing Enclosures, AS2870-2011 Residential

Synthetic Grass Covering

Supply synthetic grass covering as per description Shield Synthetic Turf

Install synthetic grass covering to concrete area, approx.. 180 square m

Complimentary Beige pitches

Rectification



Supply & lay turf to wicket surrounds, approx..60lin. m x 1m. Total 60 square metres
Damage to park ground surfaces to be levelled out and top dressed.
Clean Up Site
Remove any debris, concrete spoil & rubbish from site
Remove temporary fence

Total Price Excluding GST	\$64,995.00
----------------------------------	--------------------

Terms & Conditions

Payment terms: 50% deposit on purchase order, 25% on supply of materials on site and final 25% payment on completion and sign off.

Excludes: Council requirements (DA & BA) – Ex Gabba works.

CONDITIONS OF QUOTATION:

1. Please note that specifics of the quotation including prices and quantities are subject to confirmation prior to commencement of any work. Prices quoted cover only services nominated.
2. This quotation remains valid for 30 days from the quotation date.
3. If our quotation is accepted, work will be undertaken by employees of Gabba Sporting Products and /or our nominated sub-contractors.
4. The conditions of offer are shown in our quotation and our offer does not imply our willingness to enter into a sub-contract agreement containing conditions that differ from our offer.
5. All variations to contract must be made in writing, signed and approved by an authorised representative prior to additional work commencing.
6. Gabba Sporting Products has built its name on quality products & workmanship, all care will be taken whilst working on site. We do not accept any responsibility for any damage to buildings, services or surrounding landscapes as we will be working in conjunction with the property engineers & stakeholders.
7. It is the client's responsibility to mark out boundaries and/or have the boundary surveyed, and services such as Phone, Power, Water & Gas must be located by the client.
8. To facilitate vehicle and machine entry to the site, a suitable path is to be nominated by the client. The client is to provide ground protection mats in place if the path is soft & likely to be damaged.
9. Unless otherwise specified, quotations are based on standard soil conditions for excavation. In the event of rock, hard fill or foreign material being encountered, further costs as required for excavation / earthwork will be applied.
10. This quote is subject to site inspection. If the work site is found to contain unforeseen obstacles, resulting in need for additional earthwork, structural support etc., this quote will no longer be valid and a new quote will be issued.
11. All soil lifted during excavation will be moved within the grounds, no soil will be removed from the property, a suitable location will be arranged with the grounds staff prior to excavation work starting.
12. Whilst every effort is made to complete the works within a timely manner, deviation from the anticipated time frame may be encountered in unfavourable weather conditions or where unforeseen obstacles are encountered within the site.
13. Site specific inductions that exceed thirty (30) minutes in length will incur a charge based on our hourly rate.
14. In the event of a dispute, the client agrees to provide details of the dispute in writing within 7 days of receipt of our invoice. If no details are provided within this time, all due monies are to be paid as per our agreed trading terms.
15. Notwithstanding the Terms & Conditions outlined above, these terms will not negate any state or federal regulation in any way.

Accepting the above works, items, notes & payment terms

Full Name: _____ Signature: _____ Date: _____

Kind Regards Mitch Gaskell

