

November 2022

Quotation

Supply, Deliver & Install

Paynesville Cricket Club

Paynesville Cricket Club - 3 Lane Facility



P: +61 7 3394 4200 W: www.gabba.com.au E: info@gabba.com.au

Cost Breakdown

Paynesville Cricket Club - 3 Lane Facility

PRELIMINARIES

Mobilisation and Site Establishment, including any temporary fencing and signage.

Preparation and submission of Management Plans to address all Health, Safety, Environmental and Quality requirements of the project, including set-out and level/grade control

DEMOLITION AND CLEARING

Demolition, removal and disposal of existing cricket nets

Clear and strip grass and topsoil from work area, stockpile for reinstatement (allow for up to 100mm of topsoil)

EARTHWORKS & REINSTATEMENT

Excavation to subgrade level under slab (225mm below Finished Surface), stockpile for filling as required, and dispose of excess off-site.

Compact subgrade beneath slab area and prepare for pavement layers

Fill area around to 100mm below finished surface using general non-structural fill, won from excavation

Reinstate disturbed areas around slab with 100mm (min) of good quality topsoil, won from site, or sourced offsite (as provisional item) blend modified surface into existing, ensuring all surfaces are free-draining

Sow suitable outfield grass seed on disturbed areas

PRACTICE PITCH AND SURROUND - SUB-BASE, CONCRETE AND SYNTHETIC SURFACE

Supply and place sub-base - 100mm thick Class 2 Crushed Rock, compacted to 98% maximum dry density (modified)

Supply and place practice pitch base slab, comprising 32MPa concrete, 125mm thick, SL72 mesh (2 layers), includes saw-cut construction joint as per drawings

Supply and install Synthetic Grass Pitch (including linemarking) comprising heavy duty 9-11mm synthetic grass (3 pitches x 2.4m x 20.12m)

Supply and install Synthetic Grass surround comprising heavy duty 20mm synthetic grass with rubber granules (3 pitches x 3.6m x 36m, excluding pitch area)

FENCING AND NETTING

Three-sided wire chain-mesh fence as shown in drawings (2 x 24.0m long, x 11.7m wide, with posts at 3m spacing (typical) including all fittings and footings. Includes all fence posts and roof net posts (integral with fence), as per Steel Post and Rail Schedule (drawing 2666/1003)

Supply and Install fabric netting curtains to form roof and sides of practice pitches, comprising:

Ally Net Posts (DN90 (101.6 x 5.0mm) Heavy Grade - Galvanised, as per Steel Post and Rail Schedule

Ally Nets (3.0m high x 23.4m long) - retractable, as per drawings and specification

Rear Net (3.0m high x 11.1m long) - fixed, as per drawings and specification

Roof Net (11.1m wide x 11.7m long) - fixed, with angled valances extending 400mm below ally nets, as per drawings and specification

Cables, clips and rigging for installation of all netting

PROVISIONAL ITEMS - GENERAL

Supply and install an additional 12m of roof netting to bring full length of roof net out to 24m - \$2940.00



+ GST

EXCLUDING
Disposal of spoil offsite

Total Price Excluding GST	\$189,255.00
----------------------------------	---------------------

Terms & Conditions

Payment terms: 50% deposit on purchase order, 25% on install of concrete slab & final 25% payment on completion & sign off.

Excludes: Council requirements (DA & BA) – Ex Gabba works.

CONDITIONS OF QUOTATION:

1. Please note that specifics of the quotation including prices and quantities are subject to confirmation prior to commencement of any work. Prices quoted cover only services nominated.
2. This quotation remains valid for 30 days from the quotation date.
3. If our quotation is accepted, work will be undertaken by employees of Gabba Sporting Products and /or our nominated sub-contractors.
4. The conditions of offer are shown in our quotation and our offer does not imply our willingness to enter into a sub-contract agreement containing conditions that differ from our offer.
5. All variations to contract must be made in writing, signed and approved by an authorised representative prior to additional work commencing.
6. Gabba Sporting Products has built its name on quality products & workmanship, all care will be taken whilst working on site. We do not accept any responsibility for any damage to buildings, services or surrounding landscapes as we will be working in conjunction with the property engineers & stakeholders.
7. It is the client's responsibility to mark out boundaries and/or have the boundary surveyed, and services such as Phone, Power, Water & Gas must be located by the client.
8. To facilitate vehicle and machine entry to the site, a suitable path is to be nominated by the client. The client is to provide ground protection mats in place if the path is soft & likely to be damaged.
9. Unless otherwise specified, quotations are based on standard soil conditions for excavation. In the event of rock, hard fill or foreign material being encountered, further costs as required for excavation / earthwork will be applied.
10. This quote is subject to site inspection. If the work site is found to contain unforeseen obstacles, resulting in need for additional earthwork, structural support etc., this quote will no longer be valid and a new quote will be issued.
11. All soil lifted during excavation will be moved within the grounds, no soil will be removed from the property, a suitable location will be arranged with the grounds staff prior to excavation work starting.
12. Whilst every effort is made to complete the works within a timely manner, deviation from the anticipated time frame may be encountered in unfavourable weather conditions or where unforeseen obstacles are encountered within the site.
13. Site specific inductions that exceed thirty (30) minutes in length will incur a charge based on our hourly rate.
14. In the event of a dispute, the client agrees to provide details of the dispute in writing within 7 days of receipt of our invoice. If no details are provided within this time, all due monies are to be paid as per our agreed trading terms.
15. Notwithstanding the Terms & Conditions outlined above, these terms will not negate any state or federal regulation in any way.

Accepting the above works, items, notes & payment terms

Full Name: _____ Signature: _____ Date: _____

Kind Regards Amanda Willcox

