



Quotation

St. Ignatius College - Athelstone SA

P: +61 7 3394 4200 W: www.gabba.com.au E: info@gabba.com.au

Cost Breakdown

6 lane cricket facility

Site specific engineering inc Geotech - \$2,990

Site establishment

Site Safety Documents

Copies of required Licences and Insurances

Safety perimeter temporary fencing

Remove the existing netting, posts & synthetic grass - \$2,047

Base cut and level 33.5m X 22.1m and 46Lm X 500mm spoon drain . Store all spoil in top car park
expected spoil 40 tonne - \$3,007.00

Base prep 740sq of area with 100mm pm20 road base and compact allowance 160 tonne road base as
per engineering supplied by St Ignatius College - Mlei consulting dwg - 2021-11346 attached. - \$18,040.00

Excavate 22 X piers @ 600mm wide X 2000mm deep , dump off site spoil from holes. Install into piers 22
X 150nb HD posts to be powder coated satin black. - \$25,135.00

Trenching and piers to excavate perimeter trenches and internal trenching no more than 4m apart north
and south and 4m apart west and east trenches to be 300mm wide by 350mm deep with four continuous
n12 rod with ligatures every 600mm and pier at every intersection 350mm round by 600mm deep with 4
n12 rods cranked one into each trench into trench. Spoil to be stored in top carpark approximate 100
tonne . Concrete is 25mpa vibrated in all beams , concrete allowance beams 50m3, piers allowance 17m3
includes concrete pump. - \$56,323.30

Spoon drain 500mm wide 300mm thick at top edge 50mm deep continuous spoon drain 42Lm plumbed
into existing sump 4 X N12 rods spaced evenly thru spoon drain inside edge of drain to be dowelled to
cricket pitch - \$11,166.10

Cricket pitch slab 33.5 Lm X 22.1 Lm X 100mm thick . SL92 mesh on plastic on chairs . Danley 6mm
dowel in cradles 44 Lm across control joints as marked , note slab needs to be 120mm thick in these
areas. Danley diamond dowels every 600mm on construction joint 58 needed. - \$65,837.20

Cut and remove some parts of existing cricket pitches and cut trenching through sections as required.
Spoil to be removed to car park , concrete to be disposed of. - \$8,305.00

As dictated by ffl on data provided 1/3 of slab will need 370mm on average and 1/3 will need 240mm of
rubble blowing out total volume from 160 tonne to approximately 260 tonne . As this is hard to
determine without sufficient ground levels an extra 100 tonne at rate of \$ 96.00 /tonne to supply and
compact. - \$10,560.00

Install Gabba Grass 32m x 22m beige pitches with green surrounds

Install 7 Gabba retractable netting storage cabinets



Install 7 heavy duty retractable lane nets 25m x 3.6m. 20mm bottom rope
Install 1 heavy duty back net 22m x 3.6m. 20mm bottom rope
Install 1 safety roof net 32m x 22m with side safety curtains.
Install with all stainless steel fittings & accessories.
- \$82,438.40

Total Price Excluding GST	\$285,859.00
----------------------------------	---------------------

Terms & Conditions

Payment terms: 50% deposit on purchase order, 25% on supply of materials on site and final 25% payment on completion and sign off.

Excludes: Council requirements (DA & BA) – Ex Gabba works.

CONDITIONS OF QUOTATION:

1. Please note that specifics of the quotation including prices and quantities are subject to confirmation prior to commencement of any work. Prices quoted cover only services nominated.
2. This quotation remains valid for 30 days from the quotation date.
3. If our quotation is accepted, work will be undertaken by employees of Gabba Sporting Products and /or our nominated sub-contractors.
4. The conditions of offer are shown in our quotation and our offer does not imply our willingness to enter into a sub-contract agreement containing conditions that differ from our offer.
5. All variations to contract must be made in writing, signed and approved by an authorised representative prior to additional work commencing.
6. Gabba Sporting Products has built its name on quality products & workmanship, all care will be taken whilst working on site. We do not accept any responsibility for any damage to buildings, services or surrounding landscapes as we will be working in conjunction with the property engineers & stakeholders.
7. It is the client's responsibility to mark out boundaries and/or have the boundary surveyed, and services such as Phone, Power, Water & Gas must be located by the client.
8. To facilitate vehicle and machine entry to the site, a suitable path is to be nominated by the client. The client is to provide ground protection mats in place if the path is soft & likely to be damaged.
9. Unless otherwise specified, quotations are based on standard soil conditions for excavation. In the event of rock, hard fill or foreign material being encountered, further costs as required for excavation / earthwork will be applied.
10. This quote is subject to site inspection. If the work site is found to contain unforeseen obstacles, resulting in need for additional earthwork, structural support etc., this quote will no longer be valid and a new quote will be issued.
11. All soil lifted during excavation will be moved within the grounds, no soil will be removed from the property, a suitable location will be arranged with the grounds staff prior to excavation work starting.
12. Whilst every effort is made to complete the works within a timely manner, deviation from the anticipated time frame may be encountered in unfavourable weather conditions or where unforeseen obstacles are encountered within the site.
13. Site specific inductions that exceed thirty (30) minutes in length will incur a charge based on our hourly rate.
14. In the event of a dispute, the client agrees to provide details of the dispute in writing within 7 days of receipt of our invoice. If no details are provided within this time, all due monies are to be paid as per our agreed trading terms.
15. Notwithstanding the Terms & Conditions outlined above, these terms will not negate any state or federal regulation in any way.

Accepting the above works, items, notes & payment terms

Full Name: _____ Signature: _____ Date: _____

Kind Regards Mitch Gaskell

