

March 2024

Quotation

Supply, Deliver & Install

University of Canberra - ACT

8 Lane synthetic & turf cricket facility - 30m



P: +61 7 3394 4200 W: www.gabba.com.au E: info@gabba.com.au

Cost Breakdown

8 Lane synthetic & turf cricket facility - 30m

Site establishment
Site specific engineering design
Site Safety Documents Site
Site Safety temporary fencing
Traffic management allowance
Copies of required Licences and Insurances
Site Set-up

Provide for a Dial B4 U Dig search for the works area and locate all services onsite before commencement of site works by means of professional ground search.

Supply, install & maintain up to 200m of Safety Bunting fencing around the works site for the duration of the works. (As per construction site diagram).

Permanently display all relevant WHS and works signage on the fencing for the duration of the works.

Provide engineering design
Construction (As per engineers specifications)
Allowance for Engineer Review of Geotechnical Report
Set-out of cricket practice nets
Excavate footings as per engineers specifications & drawings
Install steel reinforcing as per engineers specs & drawings
Install uprights as per engineers specs & drawings

Slabs & Footings
Footings and reinforcing will be inspected by rep. prior to concrete placement
Install 381.6l/m of 300 x 300 edge & internal thickening beams
Install 1 concrete slab 28.8m wide x 30m, SL 82, 25mpa
60l/m concrete line pump allowance.

Turf block 25m long x 16m wide
Excavate an area 25m long x 16m wide x 400mm deep (Turf block)
soil to be placed onsite in a suitable location.
Install a Turf wicket block inc agg stone, med sand & 150mm thick of Black wicket soil.
Washed Green couch 25m long x 16m wide (400m2)
Turfed run ups.
suitable Irrigation



Synthetic Grass Covering

Install Gabba Grass covering to concrete area 864 m2

Complimentary Beige pitches

Posts

Synthetic facility - Install 24 Engineered posts with base plate- Satin black

Turf facility - Install 21 external Engineered posts with base plate- Satin black

Netting

Install 9 Lane nets 27m long x 3.6m high - Internal nets retractable for multi use.

Install 1 back net 28.8m wide x 3.6 high

Install 1 full cover safety roof net 28.8m x 30m with side safety curtain nets

Install 4 lane retractable turf cage net 16m wide x 25m long

Fencing - fully enclosed

183.6 l/m of black pvc fencing 3.6m high

1 machinery double access gates

2 pedestrian double access gates

86.8 L/m of rubber conveyorbelt rubber protection across the back & 6m up each side

Rectification

Supply & lay turf to Slab surrounds, approx..153.6l/m x 1m.

Damage to park ground surfaces to be levelled out and top dressed.

Clean Up Site

Remove any rubbish from site

Remove temporary fence

Total Price Excluding GST

\$828,866.00

Terms & Conditions

Payment terms: 50% deposit on purchase order, 25% on install of concrete slab & final 25% payment on completion & sign off.

Excludes: Council requirements (DA & BA) – Ex Gabba works.

CONDITIONS OF QUOTATION:

1. Please note that specifics of the quotation including prices and quantities are subject to confirmation prior to commencement of any work. Prices quoted cover only services nominated.
2. This quotation remains valid for 30 days from the quotation date.
3. If our quotation is accepted, work will be undertaken by employees of Gabba Sporting Products and /or our nominated sub-contractors.
4. The conditions of offer are shown in our quotation and our offer does not imply our willingness to enter into a sub-contract agreement containing conditions that differ from our offer.
5. All variations to contract must be made in writing, signed and approved by an authorised representative prior to additional work commencing.
6. Gabba Sporting Products has built its name on quality products & workmanship, all care will be taken whilst working on site. We do not accept any responsibility for any damage to buildings, services or surrounding landscapes as we will be working in conjunction with the property engineers & stakeholders.
7. It is the client's responsibility to mark out boundaries and/or have the boundary surveyed, and services such as Phone, Power, Water & Gas must be located by the client.
8. To facilitate vehicle and machine entry to the site, a suitable path is to be nominated by the client. The client is to provide ground protection mats in place if the path is soft & likely to be damaged.
9. Unless otherwise specified, quotations are based on standard soil conditions for excavation. In the event of rock, hard fill or foreign material being encountered, further costs as required for excavation / earthwork will be applied.
10. This quote is subject to site inspection. If the work site is found to contain unforeseen obstacles, resulting in need for additional earthwork, structural support etc., this quote will no longer be valid and a new quote will be issued.
11. All soil lifted during excavation will be moved within the grounds, no soil will be removed from the property, a suitable location will be arranged with the grounds staff prior to excavation work starting.
12. Whilst every effort is made to complete the works within a timely manner, deviation from the anticipated time frame may be encountered in unfavourable weather conditions or where unforeseen obstacles are encountered within the site.
13. Site specific inductions that exceed thirty (30) minutes in length will incur a charge based on our hourly rate.
14. In the event of a dispute, the client agrees to provide details of the dispute in writing within 7 days of receipt of our invoice. If no details are provided within this time, all due monies are to be paid as per our agreed trading terms.
15. Notwithstanding the Terms & Conditions outlined above, these terms will not negate any state or federal regulation in any way.

Accepting the above works, items, notes & payment terms

Full Name: _____ Signature: _____ Date: _____

Kind Regards Mitch Gaskell

