



June 2026

Quotation

Supply, Deliver & Install

Xavier College - Kew - Victoria

8 lane Cricket facility



P: +61 7 3394 4200 W: www.gabba.com.au E: info@gabba.com.au

Cost Breakdown

8 lane Cricket facility

Site documentation:

Establishment

Safety Document / plan

Safety temporary fencing

Traffic Management plan

Copies of required Licences and Insurances

Project management

Construction certificate requirements

Geotech - supplied by Client

Engineering

Site Set-up -Supply, install 150m of safety Temp Fencing around the work site.

Permanently display all relevant WHS and works signage on the temp fencing for the duration of the works.

All work to comply with AS 1725.4 Cricket Net Fencing Enclosures,

Set-out of cricket practice nets

Excavate footings as per AS 1725.4 & AS2870-2011

Install steel reinforcing as AS 1725.4 & AS2870-2011

Install uprights as per AS 1725.4 & AS2870-2011

Slabs & Footings:

Footings and reinforcing will be inspected by certifying rep. prior to concrete placement

1 x Install concrete slab 30.8m wide x 40m long, Excavate 1% fall for drainage, F82 Reo mesh, 25 MPa concrete, 100mm thick, steel trowel finish.

Gabba Grass & Nets

1 x Gabba Grass 10mm TEST 30.8m wide x 40m long Installed -Complimentary Beige pitches.

48 x Adhesive 20lt

9 x Lane net with fittings 25m x 3.6m

1 x Back net with fittings 28.8m x 3.6m

1 x 36ply canopy net with fittings 30.8m wide x 40m Long

Fencing:

Install perimeter chain wire security fence 40m long x 30.8m wide x 3.6m High Black powdercoated.

2 x double entry gate(s)

Clean Up Site

Remove any debris, concrete spoil & rubbish from site

Remove safety fencing



VBA Warranties

Structural slab 6 years Structural

Posts 7 years materials & workmanship

Fencing 2 years materials & workmanship

Netting 5 years materials & workmanship

Synthetic grass 8 years materials & workmanship

10 lane Facility 36m wide x 40m Long - \$443,000 + GST

12 lane Facility 43.2m wide x 40m Long \$495,600 + GST

Turf Block Netting System

Engineered steel structure

Sideways retractable netting system

Stainless steel cables & fittings

Note: Turf Block 29.4m wide x 30 long

\$98,000 + GST

Total Price Excluding GST**\$373,900.00**

Terms & Conditions

Payment terms: 50% deposit on purchase order, 25% on supply of materials on site and final 25% payment on completion and sign off.

Excludes: Council requirements (DA & BA) – Ex Gabba works.

CONDITIONS OF QUOTATION:

1. Please note that specifics of the quotation including prices and quantities are subject to confirmation prior to commencement of any work. Prices quoted cover only services nominated.
2. This quotation remains valid for 30 days from the quotation date.
3. If our quotation is accepted, work will be undertaken by employees of Gabba Sporting Products and /or our nominated sub-contractors.
4. The conditions of offer are shown in our quotation and our offer does not imply our willingness to enter into a sub-contract agreement containing conditions that differ from our offer.
5. All variations to contract must be made in writing, signed and approved by an authorised representative prior to additional work commencing.
6. Gabba Sporting Products has built its name on quality products & workmanship, all care will be taken whilst working on site. We do not accept any responsibility for any damage to buildings, services or surrounding landscapes as we will be working in conjunction with the property engineers & stakeholders.
7. It is the client's responsibility to mark out boundaries and/or have the boundary surveyed, and services such as Phone, Power, Water & Gas must be located by the client.
8. To facilitate vehicle and machine entry to the site, a suitable path is to be nominated by the client. The client is to provide ground protection mats in place if the path is soft & likely to be damaged.
9. Unless otherwise specified, quotations are based on standard soil conditions for excavation. In the event of rock, hard fill or foreign material being encountered, further costs as required for excavation / earthwork will be applied.
10. This quote is subject to site inspection. If the work site is found to contain unforeseen obstacles, resulting in need for additional earthwork, structural support etc., this quote will no longer be valid and a new quote will be issued.
11. All soil lifted during excavation will be moved within the grounds, no soil will be removed from the property, a suitable location will be arranged with the grounds staff prior to excavation work starting.
12. Whilst every effort is made to complete the works within a timely manner, deviation from the anticipated time frame may be encountered in unfavourable weather conditions or where unforeseen obstacles are encountered within the site.
13. Site specific inductions that exceed thirty (30) minutes in length will incur a charge based on our hourly rate.
14. In the event of a dispute, the client agrees to provide details of the dispute in writing within 7 days of receipt of our invoice. If no details are provided within this time, all due monies are to be paid as per our agreed trading terms.
15. Notwithstanding the Terms & Conditions outlined above, these terms will not negate any state or federal regulation in any way.
16. It is the customer's responsibility to ensure sufficient access, equipment, and personnel are available to unload the entire order from the truck.

Accepting the above works, items, notes & payment terms

Full Name: _____ Signature: _____ Date: _____

Kind Regards Mitch Gaskell

